Bruhat Bangalore Mahanagara Palike
Executive Engineer Yelahanka Division

Name of Work: Construction of culverts in Kempegowda ward no-01 of Yelahanka Sub Division

							Estimate Cost	15.00 Lakhs
Description of Items	**No**	**Length**	**Width**	**Depth**	**Quantity**	**Unit**	**Rate**	**Amount**
Earth work **excavation by manual means for drains**,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work . Loading and Unloading of Stone Boulder/Stone aggregates/Sand/Kankar/Moorum.(Tipper 5.5 m3) (V-I.No 1.4,Page No-5 PWD SR 2021-22) & (V-III Page No.3, Item No.1.1 A of PWD SR 2021-22)								
Basic Rate	186.00							
Loading And Unloading	118.00							
Sub Total	304.00							
Area Weightage 10%	30.40							
Total Rate	**334.40**							
Culverts								
	3	5.00	1.80	1.00	27.00			
	5	6.00	1.80	1.00	54.00			
	4	5.50	1.80	1.00	39.60			
					120.60	**Cum**	**334.40**	**40,328.64**
Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) **Mix 1:3:6 (M10) Using 40 mm** nominal size graded crushed coarse aggregates (V-1, P.No-15, I No-2.1.3 of PWD SR 2021-22)(Issue rate on 07-07-22)								
Basic Rate	5554.00							
Area Weightage 10%	555.40							
Total Rate	6109.40							
Culverts								
	3	5.00	1.80	0.15	4.05			
	5	6.00	1.80	0.15	8.10			
	4	5.50	1.80	0.15	5.94			
					18.09	**Cum**	**6109.40**	**110519.05**
Supplying, **Fitting and Placing un-coated TMT bar** Reinforcement in sub-structure complete as per Drawing and Technical Specifications.(V-III, I.No 13.1 Page No 99, PWD SR 2021-22) (Issue rate on 07-07-22)								
Basic Rate	92170.00							
Area Weightage 10%	9217.00							
Total Rate	101387.00							
For CC Culvert, 90kg/Cum	1	37.05	90.00		3334.59			

Scanned with CamScanner

Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
					3334.59			
					3.33	Tn	101387.00	338084.08
Providing and laying in position **Reinforced cement concrete** for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately) **M20 Design Mix Using 20 mm** nominal size graded crushed coarse aggregates (V-1,P.No.17, I.No.2.4.2 of PWD SR 2021-22) Apendx I, V-I P.No-115)(Issue rate on 07-07-22)								
Basic Rate	5968.00							
5% Centring	298.40							
Sub Total	6266.40							
Area Weightage 10%	626.64							
Total Rate	6893.04							
Culvert Raft								
	3	5.00	1.50	0.20	4.50			
	5	6.00	1.50	0.20	9.00			
	4	5.50	1.50	0.20	6.60			
CulvertWall								
	6	5.00	0.23	0.55	3.80			
	10	6.00	0.23	0.55	7.59			
	8	5.50	0.23	0.55	5.57			
					37.05			
					37.05	Cum	6893.04	255394.03
Providing and fixing precast reinforced cement concrete **covering slabs of 23Cm thick** made of M25 with OPC cement,@340kgs/cum with 20mm and down size graded granite metal coarse aggregate @0.70cum and fine aggregate & 0.74 cum with superplasticizer machine,mixed, Inculding providing and removing centering, shuttering, strutting propping etc., for edges of slabs with TMT steel (Fe500) cost of all materials, labour, all lead and lift, HOM of machinery, curing, including cost of reinforcement etc., complete as directed by the Engineer in charge of the work.(Exclusive of GST and Area Loading Charges)								
Data Rate	5037.00							
RCC Culvert								
Culvert Raft								
	3	5.00	1.50		22.50			
	5	6.00	1.50		45.00			
	4	5.50	1.50		33.00			
					100.50	Sqm	5037.00	506218.50
Cost of Haulage Excluding Loading and Unloading Taking output 10 t load and lead 10 km = 100 t.km(V-III Page No.3, Item No.1.4A of PWD SR 2021-22)								
Basic Rate	12.00							
8KM Lead = 12*8	96.00							
Area Weightage 10%	9.60							
Total Rate	105.60							
Qty frm Item No-1		120.6	1.28		154.37			
					154.37	t.Km	105.60	16,301.26

Scanned with CamScanner

Description of Items	No	Length	Width	Depth	Quantity	Unit	Rate	Amount
							Total Construction Cost	1266845.55
							18% GST for Construction Cost	228032.20
							Sub Total	1494877.75
							Utility Shifting,Miscellaneous and Rounding off	5,122.25
							GRAND TOTAL	1500000.00

Certificate

1. The workspot was inspected and works is found to be necessary.
2. The area comes within the Bruhat Bangalore Mahanagara Palike limits.
3. The rates adopted based on the PWD SR,Bangalore circle for year 2021-2022, ssue rates dated 07-07-2022 and Data Rates

Assistant Engineer
Ward No-01
BBMP Bangalore

Asst. Executive Engineer,
Yelahanka Sub Division
BBMP Bangalore

Executive Engineer,
Yelahanka Division
BBMP Bangalore

Administrative Approval
Accorded For 15.00 Lakhs
Head of A/C.....
CER NO :.....32..... Dt:..22/8/2022

TA

CE (YNK),

TECHNICALLY SANCTIONED FOR Rs. 15.00 lakhs
Rupees ..Fifteen Lakhs Only.....
.....
Under .....
.....
Registered as CE ( ) No. 9 9
Subject to conditions contained in enclosed memo EE ( ) No. .....18...../9/
Dt..22/8/2022..... Estimate A/ Sanctioned
BBMP/EE/YNK.01/TS/18/22-23.....No...18.....
Dated ..22/8/2022..... Rs.....15.00 Lakhs.

Executive Engineer

Scanned with CamScanner